



TABLE A

| | | | | | | | | | | | | | | | | | |
|-----|----|----|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| "A" | 4" | 6" | 8" | 10" | 12" | 15" | 18" | 21" | 24" | 30" | 36" | 42" | 48" | 54" | 60" | 66" | 72" |
| "B" | 6" | 6" | 6" | 6" | 6" | D/2 | 24" | 24" | 24" | 24" | 24" |

TRENCH FOUNDATION STABILIZATION, AS REQUIRED

BACKFILL IN STREET AREAS

1. FILL ROCK TO BACK OF S/W.
2. FILL ROCK 2' FROM FINISHED GRADE IN PLANTER AREAS.
3. ASPHALT SPECIFICATIONS AND DEPTH PER PUBLIC WORKS STANDARDS AND STREET CLASSIFICATION.
4. CONCRETE PANEL REPLACEMENT PER DESIGN AND DOWELED TO SURROUNDING PANELS OR CURB.
5. BACKFILL IN ODOT ROADWAYS PER ODOT STANDARDS.
6. WHEN PIPE COVER IS 2 FEET OR LESS, BACKFILL WITH CLSM PER PROJECT SPECIFICATIONS OR PER ODOT STANDARD SPECIFICATION 00442 WHEN PROJECT IS SILENT ON REQUIREMENTS.

Detail Drawing may not be altered or changed in any manner except by the Public Works Director. It is the responsibility of the user to acquire the most current version.

CITY OF MOLALLA
DEPARTMENT OF PUBLIC WORKS



STANDARD TRENCH DETAIL

| | | |
|------------|----|---------|
| DRAWN BY | PW | 01/2020 |
| CHECKED BY | GF | 01/2020 |

S-2140