



NOTES:

1. ALL FABRICATED METAL PARTS SHALL BE HOT-DIPPED GALVANIZED AFTER FABRICATION.
2. CONCRETE SHALL ATTAIN A MIN. COMPRESSIVE STRENGTH OF 3000 PSI. IN 28 DAYS.
3. PRECAST CURB INLET SHALL BE UTILITY VAULT 30" CURB INLET TOP #CI-30-23FC OR APPROVED EQUAL..
4. INSTALL STEPS WHEN DISTANCE FROM TOP OF LID TO FLOW LINE OF PIPE IS GREATER THAN 4 FEET.

Detail Drawing may not be altered or changed in any manner except by the Public Works Director. It is the responsibility of the user to acquire the most current version.

CITY OF MOLALLA
DEPARTMENT OF PUBLIC WORKS



30" CURB INLET
(CI-30)

DRAWN BY PDG 03/2017

CHECKED BY GF 03/2017

S-2085