

NOTES

- I. DITCH INLET CONSTRUCTION IN ACCORDANCE WITH ASTM C-478.
- 2. REQUIRED TO BE BEDDED IN 8" OF COMPACTED 3/4"-O CRUSHED ROCK BASE MATERIAL.
- 3. PRIOR APPROVAL REQUIRED FOR DITCH INLET STRUCTURES FOR PIPE SIZES 24" OR LARGER.
- 4. PRECAST DITCH INLET SHALL BE UTILITY VAULT ODOT TYPE G2 INLET OR APPROVED EQUAL.

Detail Drawing may not be altered or changed in any manner except by the Public Works Director. It is the responsibility of the user to acquire the most current version.

CITY OF MOLALLA DEPARTMENT OF PUBLIC WORKS



| G2 | DITCH | INLET |
|----|-------|-------|
|----|-------|-------|

| DRAWN BY | PDG | 30/2017 | U |
|------------|-----|---------|---|
| CHECKED BY | GF | 03/2017 |) |

5-2120